## DEAUFORT SCALE

NO WORKING OUTDOORS

## **CONSTRUCTION SAFETY**

WIND SPEED / ANEOMETER READING				
FORCE	KM/H	DESCRIPTION	EFFECT ON LAND	SAFETY
0	<1	Calm	Smoke rises vertically; Wind vains still	prosafetygear.com GEAR
	1-5	Light Air	Smoke drift indicates wind direction; Wind vains still	WORKING IN THE WIND
2	6-11	Light Breeze	Leaves rustle; Wind felt on face; Wind vanes moved by wind	
3	12-19	Gentle Breeze	Leaves and twigs constantly moving; Light flags extended	SAFETY PRECAUTIONS
4	20-29	Moderate Breeze	Dust and loose paper raised; Small branches move	Safety glasses should be worn to protect against dust and foreign particles.
5	30-38	Fresh Breeze	Large branches move; Small trees with leaves begin to sway Wind can lift scrap metal & carry it as far out as the height from which it came.	Hard hats should be worn and securely fastened.  Loose materials should be secured and tools packed up safely when not in use.
6	39-50	Strong Breeze	Larger tree branches moving; Phone lines whistle; Empty plastic bins can blow over Wind gusts can throw you off balance	Workers at elevations above 1m should exercise caution. Use extreme care when picking up large sections of plywood or similar flat materials. Tag lines should be used when hoisting loads with large flat surfaces that can act as a sail.
				_
7	51-61	Near Gale	Whole trees moving; Wind is difficult to walk against	Hoisting equipment and mobile access equipment should not be used unless approved by safety manager. Follow manufacturer's guidlines on the max wind speed at which MEWP can be safely operated.
8	62-74	Gale	Twigs break off trees; Wind is difficult to walk against; Cars veer on road; Construction signs & barricades blow over	No working at heights including roofs and scaffolding.  Crane operation should cease and cranes be secured and / or dismantled.  Exercise caution when working near partially built walls and structures. Check that
				structures are braced and well supported
9	75-86	Strong Gale	Larger branches break off trees; Minor damage to buildings; Shingles & slates torn off roofs	Secure roofing sheets, cones, bollards and any other equipment.  Canapies / tents should be dismantled
September Strategy	87-101	Storm	Trees uprooted; considerable structural damage to buidlings	
	102-115	Violent Storm	Widespread damage	NO WORKING AT HEIGHTS BEYOND THIS POINT
	>115	Hurricane	Widespread damage	ALL WORK TO BE CEASED BEYOND THIS POINT